WINDSOR WIRE
BUNDLED CABLE TECHNOLOGIES

Call: 802.674.6555
31 National Road • Edison, NJ 08817
www.windsorwireco.com

## REDUCE MAN HOURS AND JOB COST BY 75% WITH

# THE RAPIDPULL™

Pulling wire in the traditional way in a highly competitive market and meeting customer tight deadlines is highly inefficient. Get today's tough wiring jobs done quickly, easily, and cost-effectively with our cable pulling systems. Our RapidPull system is designed to help you save time, save on labor costs, as well as reduce material costs. When speed, accuracy, and convenience are at the top of your "must have" feature list for wire feed systems, make sure you're using RapidPull!

Get the job done fast, and get it done right, with the original RapidPull System!

| TOTAL TIME TO PULL CIRCUIT WIRE | | | | TRADITIONAL | RAPIDPULL |
|---|---|---|---|---|---|
| | Length | # of Conductor | Total Wire Footage | Total Time | Total Time |
| **Setup Time** | | | | **20** | **13** |
| Run 1 | 106 | 7 | 742 | 29 | 6 |
| Run 2 | 109 | 7 | 763 | 27 | 5 |
| Run 3 | 126 | 7 | 882 | 28 | 7 |
| Run 4 | 119 | 7 | 833 | 29 | 6 |
| Run 5 | 106 | 9 | 954 | 34 | 5 |
| Run 6 | 109 | 9 | 981 | 37 | 6 |
| Run 7 | 127 | 9 | 1143 | 34 | 7 |
| Run 8 | 119 | 9 | 1071 | 32 | 7 |
| **Breakdown** | | | | **8** | **2** |
| ***TOTAL (MINUTES)*** | | | | ***278*** | ***64*** |
| ***TOTAL (MANHOURS)*** | | | | ***4.63*** | ***1.07*** |

PULL 8 CONDUITS VARYING LENGTHS OF #10 THHN STRANDED WITH 2 MEN PER PULL. THIS IS A 75% LABOR SAVINGS USING OUR RAPIDPULL SYSTEM.
THIS TIME TRIAL WAS PERFORMED BY A LARGE ELECTRICAL CONTRACTOR TO TEST AGAINST OUR LABOR SAVING CLAIMS.